GOVERNMENT OF TELANGANA
ABSTRACT

Irrigation & CAD Department – Mission Kakatiya – Administrative Approval for the work "Improvements to Patel Cheruvu, Amma Kunta, Thatha Kunta of Zapthishivanoor (V), Narsingi Mandal, Medak District" for an amount of Rs.59,00,000/- – Accorded – Orders – Issued.

IRRIGATION & CAD (MK) DEPARTMENT

G.O.Rt.No. 336 **Dated: 01-12-2025**

Read:-

From the Engineer-in-Chief (General), Irrigation &CAD Department, Hyderabad, Lr.No.ENC(G)/CE(MI)/ DyENC(G)/DCE(MI)/DEE11/AEE29/ Zapthishivanoor Estimates, Dt: 16-05-2025.

@@@

ORDER:

Under the circumstances reported by the Engineer-in-Chief (General), Irrigation & CAD Department, Hyderabad in the reference read above, after careful examination of the proposal, Government hereby accord Administrative Approval for an amount of Rs.59,00,000/- (Rupees Fifty Nine Lakhs only) for the work "Improvements to Patel Cheruvu, Amma Kunta, Thatha Kunta of Zapthishivanoor (V), Narsingi Mandal, Medak District", subject to the following conditions:-

i) The Chief Engineer (I), Gajwel is responsible for correctness of quantities, rates adopted and provisions made in the estimate.

ii) The Chief Engineer (I), Hyderabad shall adhere to the following guidelines, to take up and complete the De-silting works.

a) The area of De-silting is to be identified in consultation with revenue authorities to avoid legal complications after grounding the work.

b) The total quantity of silt to be excavated is to be scientifically assessed.

c) Preliminary studies like, what is the actual capacity of the project, what is the present capacity, how much silt accumulated, how much silt can be removed as per the MK guidelines without compromising the functionality, whether the proposed quantity of the silt is within accumulated silt quantity or not etc, shall be done before taking up the work.

d) To arrive the quantum of silt to be removed net levels at every 15 meters interval shall be taken in the bed area along with Quality Control staff.

e) The depth up to which silt can be removed safely, shall be assessed judiciously, ensuring minimum depth of impermeable layer of silt on the bed is maintained, else there is a possibility of stored water percolating through the bed, particularly in sandy / highly permeable bed soil areas.

f) To ascertain the same, trail pits at every (50 or 100) meters interval, in tank bed, up to original ground strata may be taken depending upon the water spread area of the tank.

g) The excavation of silt has to be done, maintaining a uniform gradient, from the FTL contour to sill level of the sluice of the tank.

P.T.O.

h) Before starting the de-silting work, it is to be planned meticulously how to dispose the silt removed, like allowing farmers to take the silt with their own transport to apply in their fields as a manure, to dump the soil in nearby quarry pits or any other suitable areas.

i) Every cubic meter of silt excavated has to be accounted for by maintaining proper registers.

j) Photos and Videos of the de-silting work are to be taken regularly and maintained as a record.

k) Increasing the top width of the bund from 3.00m to 5.00m, duly relaxing in terms of Minor Irrigation guidelines.

iii) Meeting the expenditure with in the BE provision duly following the G.O.Ms.No.12, I&CAD (P&B) Department, Dt: 20.02.2016.

2. The above expenditure shall be debited to the Head of Account “4702-00-101-25-21-530-531”.

3. The Engineer-in-Chief (General), Irrigation & CAD Department, Hyderabad shall take necessary action accordingly.

4. This order issues with the concurrence of Finance (EBS.IX) Department, vide their U.O.No.3323675/135/A1/EBS.IX/2025, Dt: 17.10.2025.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF TELANGANA)

RAHUL BOJJA
PRINCIPAL SECRETARY TO GOVERNMENT

To
The Engineer-in-Chief (General), Errummanzil, Hyderabad.
Copy to:
The Chief Engineer (Irrigation), Errummanzil, Hyderabad.
The Accountant General, Telangana, Hyderabad.
The Director of Works & Accounts, M.J. Market Road, Hyderabad.
The PS to Hon’ble Minister (Irrigation).
The PS to Principal Secretary to Government, I&CAD Department.
SC/SF

// FORWARDED :: BY ORDER //

SECTION OFFICER